



DAV PUBLIC SCHOOL

UNIT - VIII, BHUBANESWAR, ODISHA

AFFILIATED TO CBSE, NEW DELHI, AFFILIATION No. 1530006, SCHOOL No. 15342

Ref. No. DAV(UNIT-VIII)/ 458 /2024

Date : 01-03-2024

NOTICE INVITING QUOTATIONS

QUOTATION FOR THE: - **Renovation of Sewerage Line of DAV Public School, Unit-VIII, Nayapalli, Bhubaneswar-12**

Sealed quotations are invited by the undersigned from reputed firms/contractor/agencies for Renovation of Sewerage Line in campus of the school. The interested firms/contractor/agencies may submit their quotations for the purpose by obtaining the prescribed **quotation form** from the office of the undersigned on all working days between **10.30 am to 1.30 pm during 02/03/2024 to 11/03/2024**. The quotation of the firms/contractor/agencies should be sent in sealed envelopes superscribed as "**QUOTATION FOR RENOVATION OF SEWERAGE LINE**" on **or before 11/03/2024 by 3.30pm**.

The bidders are also required to enclose a DD of **Rs.20,000/- (Rupees Twenty thousand only)** drawn in favour of "**Principal, DAV Public School, Unit-VIII, Bhubaneswar**"

The quotations will be opened in the office of the Principal, DAV Public School, Unit-VIII, Bhubaneswar **at 4.30pm on 11/03/2024**.

The rate should be inclusive of all taxes (GST)

There should not be any overwriting or corrections in the quotations.

The undersigned does not bind herself to accept the lowest quotation.

and reserves the right to accept the quotation in whole or in part thereof.

The quotations received after the stipulated date & time or incomplete in any respect shall not be considered. The quotations without GST No shall not be considered also.

The undersigned reserves the right to cancel any or all the quotation(s) without assigning any reason thereof.


PRINCIPAL

Copy to:-

- 1 The Notice Board & Website of the school for information of all concerned.
- 2 The Principal, DAV Public Schools, Bhubaneswar and Cuttack with a request to kindly take steps to display the quotation call notice on the School Notice Board and Websites for information of the public/person concerned
- 3 The concerned file for record.

DAV PUBLIC SCHOOL, UNIT-VIII, NAYAPALLI, BHUBANESWAR-12
QUOTATION FORM FOR RENOVATION OF SEWERAGE LINE.

Ph- (0674)2391328 Date- _____

Name of Agency/Firm _____

Aadhar Card No _____

PAN Card No. _____

Contractor License No _____

GST No _____

(Please enclosed if any experience)

Sl.No	Description of Work	Quantity	Rate per cum/ sqft/each
01	Construction work of Bricks masonry with excavation work GT Chamber with frame cover including all the materials along with labour charges (Plaster and punning) with proper finishing work from the ground level as per the requirement leveling from GT Chamber to IC Chamber as per direction of Engineer-In-Charge.	Sqm.	
02	Construction work of Bricks masonry with excavation work Inspection Chamber with frame cover including all the materials along with labour charges (Plaster and Punning) with proper finishing work from the ground level as per the requirement leveling from IC Chamber to IC MH chamber as per direction of Engineer-In-Charge.	Sqm.	
03	Construction work of RCC (1:1:5:3) Manhole Chamber with cover including all the materials along with labour charges with proper finishing work from the ground level as per the requirement the leveling from Manhole Chamber to existing Main MH Chamber. RCC Wall with Cover Slab 6" thickness with excavation work as per direction of Engineer-In-Charge.	Sqm	
04	Supply and Lying PVC SWR Pipe (110mm 4kg Ashribad Make) of Size-4" including cutting of tiles, concrete , earth including labour charges along with shifting the debries with back filling as per direction of Engineer-In-Charge.	Meter	
05	Supply and Lying of RCC Hume Pipe of Size-8" dia including cutting of tiles, concrete , earth including labour charges with back filling as per direction of Engineer-In-Charge.	Meter	
06	Shifting the debris and C&D materials from the school site after complete the work phase to phase as per direction of Engineer-In-Charge.	Per Trip Tractor Tripper	
07	Fixing/Making the chequered tile (GICO Make) matching with the existing one after the PCC work 1:4:8 including the materials along with labour charges with proper finishing the work as per the requirement.	Sqm	
08	Fixing/Making the chequered tile (GICO Make) matching with the existing one after the CC work 1:2:3 including the materials along with labour charges with proper finishing the work as per the requirement.	Sqm	

Please quote the rate after visit the site and note that Work completion Period within 45 days of issue of work order.

Signature with seal of Quotationer

Address :

Contact No. :